

Dow Water & Process Solutions

Subzero Operating Conditions Are No Match for DOW FILMTEC™ Seawater Reverse Osmosis Elements

FAST FACTS

Plants location: Antarctic: Rothera & Signy Research

Stations

Operation: Seawater filtration at very low

temperatures

DOW FILMTEC™ RO element: SW30-4040

Permeate flow: 15 m³/d (Rothera) and 5 m³/d (Signy)

Permeate flux: < 12 LMH
Feed water TDS: 35,011 ppm
Minimum temperature: -1.5°C
Operating pressure > 65 bar

OEM: Salt Separation Services, UK

The Rothera and Signy Research Stations, located in the Antarctic, operate 15 m³/d and 5 m³/d seawater reverse osmosis (RO) plants, respectively. Designed and built by Salt Separation Services in the United Kingdom, both facilities were fitted with DOW FILMTEC™ SW30-4040 Elements in 2003. During operation the elements are exposed to temperatures as low as -1.5°C, yet the elements show no sign of damage and have provided stable performance to the facilities for more than 12 years.

Plant Configuration

The Rothera unit, shown in Figure 1, and Signy unit consist of self-contained skid mounted plants, including: sand filter, cartridge filters, antiscalant dosing (Rothera only), a clean-in-place (CIP) system and rehardener.

Operation & Maintenance

The Rothera Research Station facility has operated for more than 12 years, providing potable water to base personnel.

During that time the elements were replaced twice after several years in operation. During the visit in 2015 the plant was found to be in excellent condition, being maintained on a regular basis by base personnel.



Stable Performance

In the first two and a half months of operation, the normalized salt rejection and permeate flow data was collected almost daily. During this time, the temperatures were between 3.4 and 1.6 °C, as shown in Figure 2 and 3.

The values in Figure 2 are compared to a Dow system design tool, Reverse Osmosis System Analysis (ROSA). The data values, equal or lower than the ROSA projected values, show excellent element performance.

The normalized permeate flow remained very stable during the data collection timeframe, indicating no effect of long term low temperature operation.










Figure 3. Normalized permeate flow registered at Rothera plant.

Water & Process Solutions

7600 Metro Blvd. Edina, MN 55439

For more information, contact our Customer Information Group:

Asia Pacific +86 21 3851 4988 Europe, Middle East, Africa +31 115 672626 +55 11 5184 8722 Latin America North America 1-800-447-4369

NOTICE: No freedom from infringement of any patent owned by Dow or others is to be inferred. Because use conditions and applicable laws may differ from one location to another and may change with time. Customer is responsible for determining whether products and the information in this document are appropriate for Customer's use and for ensuring that Customer's workplace and disposal practices are in compliance with applicable laws and other government enactments. The product shown in this literature may not be available for sale and/or available in all geographies where Dow is represented. The claims made may not have been approved for use in all countries. Dow assumes no obligation or liability for the information in this document. References to "Dow" or the "Company" mean the Dow legal entity selling the products to Customer unless otherwise expressly noted. NO WARRANTIES ARE GIVEN; ALL IMPLIED WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE ARE EXPRESSLY EXCLUDED. All information set forth herein is for informational purposes only. This information is general information and may differ from that based on actual conditions. Please note that physical properties may vary depending on certain conditions and while operating conditions stated in this document are intended to lengthen product lifespan and/or improve product performance, it will ultimately depend on actual circumstances and is in no event a guarantee of achieving any specific results. Nothing in this document should be treated as a warranty by Dow.